

Abstract Estimate For The Proposed Construction Of R.C.C Roof Residential Building In Ground Floor & First Floor (After Demolising The Building) In Ward No.02, T.S.NO:2578-B(P),Door No.6A, In Varahakulam North Street,Kumbakonam City Municipal Corporation,Thanjavur Dt.

Owner'sName: Mr.D.Rajsekar D.Sambathkumar. Total .42,00,000.00

S.No	Description of Works	Qty	Rate	Per	Amount
1.	Earthwork excavation in ordinary soil for foundation	2065.00	15.00	Cft	30975.00
2.	Sand filling for foundation and basement with clear river sand	2596.00	75.00	Cft	1,94,700.00
3.	P.C.C 1:5:10 mix using 40mm HBG metal for foundation and flooring concrete etc complete	500.00	160.,00	Cft	80,000.00
4.	R.C.C1:2:4 mix using for 12-20mm HBG metal for column, column footing ,plinth beam pedestal, lintel beam and roof slab etc	2190.00	600.00	Cft	13,14,000.00
5.	Brickwork in CM 1:6 mix using for best quality brick for basement and superstructure etc. complete.	3915.00	150.00	Cft	5,87,250.00
6.	Floor finishing CM 1:3mix with Tiles flooring work.	1502.00	150.00	Sft	2,25,300.00
7.	Ceiling plastering CM1:3 Mix	1502.00	70.00	Sft	1,05,140.00
8.	Weathering course over roof slab with brick jelly and lime concrete laying one course of pressed tiles embedded in cm 1:3 mix.	935.00	120.00	Sft	1,12,200.00

9.	Beast seasoned imported vengai wood used for doors ,windows and ventilator etc. complete.	400.00	1200.00	Sft	4,80,000.00
10.	Plastering in CM 1:5 mix using for exterior and interior wall surfaces.	11,240.00	60.00	Sft	6,74,400.00
11.	Fixing Of Glazed Tiles Wall In Kitchen & Toilet exc.			LS	75,000.00
12.	Provision For Cubboard Work			LS	
13.	Provision for Borewell			LS	60,000.00
14.	Provision of Water Supplying and Sanitary Arrangements			LS	50,000.00
15.	Provision for white washing and colour washing and painting work				1,00,000.00
16.	Providing electrification work				1,00,000.00
17.	P-S and contingencies work			LS	11,035.00
				Total	42,00,000.00

(Rupees Forty Two Lakhs Only)

V. Srinivasan
Er. V. GUNASEKARAN
Consulting Civil Engineer
Licensed Surveyor
G.V.BUILDERS
143, John Selvaraj Nagar
Kumbakonam - 612 001
Cell: 98944 22913

Detailed Estimate For The Proposed Construction Of R.C.C Roof Residential Building In Ground Floor & First Floor (After Demolising The Building) In Ward No.02, T.S.NO:2578-B(P), Door No.6A, In Varahakulam North Street, Kumbakonam City Municipal Corporation, Thanjavur Dt.

Owner's Name: Mr.D.Rajsekar D.Sambathkumar

S.NO	Description Of Works	NOS	L	B	D	QTY
1.	Earthwork excavation in ordinary soil for foundation					
	column	1x16	4'0"	4'0"	6'0"	1536.00
	Plinth beam	1X1	234'0"	1'6"	1'6"	526.50
	Sundries					2.50
					Total	2065.00Cft
2.	Sand filling for foundation and basement with clear river sand					
	column	1x16	4'0"	4'0"	1'0"	256.00
	Plinth beam	1X1	234'0"	1'6"	0'3"	87.75
	Basement					
	Parking	1X1	9'6"	14'0"	3'0"	399.00
	Living	1X1	9'6"	18'0"	3'0"	513.00
	Bed&Passage	1X1	9'6"	12'9"	3'0"	363.38
	Kitchen&Passage	1X1	9'6"	11'3"	3'0"	320.63
	Toilet&Passage	1X1	9'6"	4'0"	3'0"	114.00
	Passage&Toilet	1X1	9'6"	5'0"	3'0"	142.50
	Bed	1X1	9'6"	14'0"	3'0"	399.00
	sundries					0.74
					Total	2596.00Cft
3.	P.C.C 1:5:10 mix using 40mm HBG metal for foundation and flooring concrete etc complete					
	Foundation					
	column	1x16	4'0"	4'0"	0'6"	128.00
	Plinth beam	1X1	234'0"	1'6"	0'3"	87.75
	Basement					
	Parking	1X1	9'6"	14'0"	0'4.5"	49.88
	Living	1X1	9'6"	18'0"	0'4.5"	64.13

	Bed&Passage	1X1	9'6''	12'9''	0'4.5''	45.42
	Kitchen&Passage	1X1	9'6''	11'3''	0'4.5''	40.08
	Toilet&Passage	1X1	9'6''	4'0''	0'4.5''	14.25
	Passage&Toilet	1X1	9'6''	5'0''	0'4.5''	17.81
	Bed	1X1	9'6''	14'0''	0'4.5''	49.88
	sundries					2.80
					Total	500.00 Cft
4.	R.C.C1:2:4 mix using for 12-20mm HBG metal for column, column footing ,plinth beam pedestal, lintel beam and roof slab etc					
	Column	1X16	0'9''	0'9''	15'3''	137.25
	Mat	1X16	4'0''	4'0''	1'0''	256.00
	Plinth beam	1X1	234'0''	0'9''	1'0''	175.50
	Lintel Beam	1X1	234'0''	0'9''	0'9''	131.63
	Roof Slab	1X1	11'0''	85'0''	0'5''	392.70
	First Floor					
	Column	1X16	0'9''	0'9''	15'3''	137.25
	Mat	1X16	4'0''	4'0''	1'0''	256.00
	Plinth beam	1X1	234'0''	0'9''	1'0''	175.50
	Lintel Beam	1X1	234'0''	0'9''	0'9''	131.63
	Roof Slab	1X1	11'0''	85'0''	0'5''	392.70
	Sundries					3.84
					Total	2190.00Cft
5.	Brickwork in CM 1:6 mix using for best quality brick for basement and superstructure etc. complete.					
	Basement					
	Main wall alround	1X1	177'0''	0'9''	2'6''	331.88
	Cross Wall	1X1	57'0''	0'9''	2'6''	106.88
	Superstructure					
	Main wall alround	1X1	177'0''	0'9''	9'3''	1227.93
	Cross Wall	1X1	57'0''	0'9''	9'3''	395.43
	First Floor					

	Superstructure					
	Main wall alround	1X1	177'0''	0'9''	9'3''	1227.93
	Cross Wall	1X1	57'0''	0'9''	9'3''	395.43
	Parapet wall	1X1	177'0''	0'9''	3'0''	398.25
	Deduction (G.F,F.F)					
	D - Door	1X2	3'3''	0'9''	7'0''	34.13
	D1 - Door	1X4	3'0''	0'9''	7'0''	63.00
	D2 - Door	1X4	2'6''	0'9''	7'0''	13.13
	W - Window	1X6	5'0''	0'9''	4'6''	16.88
	W1 - Window	1X2	4'0''	0'9''	4'6''	27.00
	V - Ventilator	1X4	3'0''	0'9''	2'0''	18.00
	Sundries					3.41
					Total	3915.00Cft
6.	Floor finishing CM 1:3 MIX With Tiles Flooring Work.					
	Parking	1X1	9'6''	14'0''	-	133.00
	Living	1X1	9'6''	18'0''	-	171.00
	Bed&Passage	1X1	9'6''	12'9''	-	121.13
	Kitchen&Passage	1X1	9'6''	11'3''	-	106.88
	Toilet&Passage	1X1	9'6''	4'0''	-	38.00
	Passage&Toilet	1X1	9'6''	5'0''	-	47.50
	Bed	1X1	9'6''	14'0''	-	133.00
	First Floor					
	Parking	1X1	9'6''	14'0''	-	133.00
	Living	1X1	9'6''	18'0''	-	171.00
	Bed&Passage	1X1	9'6''	12'9''	-	121.13
	Kitchen&Passage	1X1	9'6''	11'3''	-	106.88
	Toilet&Passage	1X1	9'6''	4'0''	-	38.00
	Passage&Toilet	1X1	9'6''	5'0''	-	47.50
	Bed	1X1	9'6''	14'0''	-	133.00
	Sundries					0.98
					Total	1502.00Sft
7.	Ceiling plastering in CM 1:3 mix					
	As Per Same Item No.6					
					Total	1502.00Sft

8.	Weathering course over roof slab with brick Jelly and lime concrete laying one course of Pressed tiles embedded in CM 1:3 Mix					
	Roof Slab area	1X1	11'0''	85'0''	-	935.00
					Total	935.00Sft
9.	Best seasoned Imported vengaa wood used For doors, windows aand ventilator etc complete.					
	D - Door	1X2	3'3''	-	7'0''	45.50
	D1 - Door	1X4	3'0''	-	7'0''	84.00
	D2 - Door	1X4	2'6''	-	7'0''	70.00
	W - Window	1X6	5'0''	-	4'6''	135.00
	W1 - Window	1X2	4'0''	-	4'6''	36.00
	V - Ventilator	1X4	3'0''	-	2'0''	24.00
	Sundries					6.00
					Total	400.00Sft
10	Plastering in CM 1:5 mix using for exterior and interior wall surface					
	Exterior Wall Surface:					
	Main Walls Alround(G.F,F.F)	1X1	189'0''	-	27'0''	5103.00
	Parapet Wall	1X1	189'0''	-	3'9''	708.75
	Interior Wall Surface					
	Parking	1X1	47'0''	-	10'0''	470.00
	Living	1X1	55'0''	-	10'0''	550.00
	Bed&Passage	1X1	44'6''	-	10'0'	445.00
	Kitchen&Passage	1X1	41'6''	-	10'0''	415.00
	Toilet&Passage	1X1	27'0''	-	10'0''	270.00
	Passage&Toilet	1X1	29'0''	-	10'0''	290.00
	Bed	1X1	47'0''		10'0''	470.00
	First Floor					
	Interior Wall Surface					
	Parking	1X1	47'0''	-	10'0''	470.00

	Living	1X1	55'0''	-	10'0''	550.00
	Bed&Passage	1X1	44'6''	-	10'0''	445.00
	Kitchen&Passage	1X1	41'6''	-	10'0''	415.00
	Toilet&Passage	1X1	27'0''	-	10'0''	270.00
	Passage&Toilet	1X1	29'0''	-	10'0''	290.00
	Bed	1X1	47'0''		10'0''	470.00
	Deduction					
	D - Door	1X2	3'3''	-	7'0''	45.50
	D1 - Door	1X4	3'0''	-	7'0''	84.00
	D2 - Door	1X4	2'6''	-	7'0''	70.00
	W - Window	1X6	5'0''	-	4'6''	135.00
	W1 - Window	1X2	4'0''	-	4'6''	36.00
	V - Ventilator	1X4	3'0''	-	2'0''	24.00
	Sundries					2.25
					Total	11240.00Sft
11	Fixing Of Glazed Tiles Wall In Kitchen & Toilet exc					LS
12	Provision For Cubboard Work					LS
13	Provision for Borewell					LS
14.	Provision of Water Supplying and Sanitary Arrangements					LS
15.	Provision for white washing and colour washing and painting work					LS
16.	Providing electrification work					LS
17	P-S and contingencies work					LS

V. GUNASEKARAN
 Er. V. GUNASEKARAN
 Consulting Civil Engineer
 Licensed Surveyor
 G.V.BUILDERS
 143, John Selvaraj Nagar
 Kumbakonam - 612 001
 Cell: 98944 22913