

Er.K.JAYAKUMAR

BE., AMIE., FIV., C. Eng.,
Chartered Engineer & Registered Valuer

3/154, N.G.G.O. Colony
A- Sangampalayam
Mahalingapuram Post
Pollachi – 642 002
8248521943, 9965554280

Valuation Report for Sundaram Home Finance

(Land& Building Method)

Type of loan	LAP	TRN	PCH20240107		
Customer Name	Thiru.S.Rajasekar	Inspection Date	09.11.2023		
Purpose of Valuation	Commercial	Type of property	Commercial Complex		
Primary Security Property details					
Property Address					
Project Name					
Address	Door No-19,T.S.No-558/Part &559/Part, Meenakshni Mall, Marappan Street, Pollachi Town, Pollachi Taluk, Pollachi SRO, Coimbatore RD				
Location	Marappan Street	City/Village	Pollachi Town		
State	Tamilnadu	Country	INDIA		
Pincode	642 002.	Landmark	It is situated very Busy Business area of Pollachi Town-Opposite to Pollachi Taluk office		
Property Details					
Property within GEO Limits	Yes	Civic Status/Jurisdiction	Municipality	Easy of Identification	Opposite street of Taluk office
Plot Demarcation	Yes	Char of f Property	Intermediate	Shape of land	Rectangular
Road 1	Type	Bitumen Road	Width	23	Feet
Road 2	Type		Width		Feet
Legal Aspects					
Name Of the Reported Owner/ Tenant	Thiru.K.P.Sundaram S/o.Late.Thiru.Palnisamy		EB Service No. /Property ID no	Available	
Approval Details					
Type of Approval	Approval status		Approval details		Approval authority
Layout approval	No		Nil		Nil
Planning Permit/ Commencement Certificate	No		Nil		Nil
Building Permit/ Occupancy Certificate	Yes		B.A.No-14/17/G3 & B.L.No: 13/17/G3 Date: 20.02.2017		The Commissioner Pollachi Municipality
Boundaries					
	North By	South By	East By	West By	
As per Document	23 feet Layout road	Property of N.Eswari	Property of S.Revathi	Property of Aravindh Sadiskumar	
As per Site	23 feet Layout road	RCC Building of N.Eswari	RCC Building of S.Revathi	Vacant site of Aravindh Sadiskumar	
Matches Document	Yes				



Nature Of Locality								
Development(locality)	Fully Developed			Approximate Number Of House		17		
				Distance From Developed Colony		Very close		
Surrounding Usage	Commercil			Classification Of Locality		Upper Middle Class		
Facility Available	Electrical Line, Road, Street Light			Water Supply		Bore Well, Municipal Water		
Sanitary System	Septic Tank							
Valuation-General								
Usage Of the Property-Plan	Commercial			Usage Of the Property-Site		Commercial Complex		
Caution Property	No			Factor Caution Property		Nil		
Factor Enhances Prop. Mkt Value	N.A			Factor Affects Prop. Mkt Value		N.A		
Marketability Of the Property	Good			Approximate rent/month		Rs.1,00,000/- & Above		
Valuation -Aspects &Age Details								
No of floor	G+1			Number of Units		1		
Unit Details	1			Occupancy status		Rented		
Construction Status	All Portions are Occupied							
Structure	Framed Structure							
Roof	RCC							
Flooring	Vitrified Ceramic Tiles							
Year of Construction	2018	Age	5.00 Years	Total life	60 Years	Residual life	55	
Age Remarks	5.00 Years old							
Protection Against Natural Disasters	Yes			Quality of Construction		Good (II nd Quality)		
Facilities Available	Commercial-Shops			% Of Building Completed		100%		
Adherence to sanction plan	Yes			Comments on sanction plan		20.02.2017		
Property Documents								
Document Name	Sale Deed No : 160/2017, Dt : 09.01.2017 in the Name of Thiru.K.P.Sundaram							
Valuation								
Land Valuation	Extent of Land (in Sq Feet)		Prevailing Market Rate (in Rs./Sq Feet)		Adopted Land Rate (in Rs./Sq Feet)		LandValue (in Rs.)	Guideline Value (in Rs.)
	1194.36		10,000-12,000		10,750/-		1,28,39,370/-	12,97,075/-
Building Valuation		Area (in Sq Feet)			Valuation (in Rs.)			
	Existing BUA	Proposed BUA	Total BUA	Existing Bldg Value	Proposed Bldg value	Total Bldg value		
As per plan-GF	499.25	--	499.25	11,08,335/-	--	11,08,335/-		
First Floor	499.25	--	499.25	10,15,974/-	--	10,15,974/-		
						21,24,309/-		
As per site-GF	1000	--	1000	22,20,000/-	--	22,20,000/-		
First Floor	1000	--	1000	20,35,000/-	--	20,35,000/-		
						42,55,000/-		
Considered Value	Area in Sq Feet			Building Value (in Rs.)		Present Building Value (inRs.)		
	2000			42,55,000/-		42,55,000/-		
Final Value	Amenities Service Cost (in Rs.)	Total Value (In Rs.)		Forced Sale Value (%)		Forced Sale Value (in Rs.)		
	Rs.10,05,000/-	1,80,99,370/- Say 1,81,00,000/-		90%		1,62,90,000/-		



Insurance					
Cost of Insurance	Rs.46,00,000/-	Property Type	Commercial Complex	Property Sub type	Commercial Complex
Comments					
Note					
1. As per Actual Construction is More than the Approval Area(Approval has Given for G+1,But the Actual Construction has done as G+3					
2. Value has Considered only for G+1 Area.					
3. The Ground Floor Building cost has considered As Rs.2500/- and the First Floor has considered as Rs.2,250/-					
4. The Value of Depreciation is 7.50%					
Appraiser Name	Er.K.Jayakumar		Recommended	Yes	
Reason	Nil				

Existing Building Area (in Sq Feet)							
Floor	Area as per Plan	Area as per Actual	Area -Rate	Cost as per Plan	Cost as per Actual	Units - Approved	Units-Actual
BASEMENT							
MEZZANINE							
Ground Floor	499.25	1000	2220/-	11,08,335/-	22,20,000/-	1	4
First Floor	499.25	1000	2035/-	10,15,974/-	20,35,000/-	1	4
SECOND FLOOR							
THIRD FLOOR							
FOURTH FLOOR							
TOTAL	988.50	2000	4255/-	21,24,309/-	42,55,000/-	2	3

Proposed Building Area (inSqFeet)							
Floor	Area as per Plan	Area as per Actual	Area -Rate	Cost as per Plan	Cost as per Actual	Units - Approved	Units-Actual
BASEMENT							
MEZZANINE							
GROUND FLOOR							
FIRST FLOOR							
SECOND FLOOR							
THIRDFLOOR							
FOURTH FLOOR							
TOTAL							

Amenities and Services	
Type	Amount (in Rs.)
Amenities	Bore Well=Rs.1,00,000/-,EB-3Services=Rs.4,55,000/-(16 Services) Outer Floor=Rs.50,000/- Staircase/Head room=Rs.4,00,000/-
Total	Rs. 10,05,000/-



Deviation		
Nature of Deviation	As per Plan /By Law	As per Site/ Actual
Plot coverage	41%	84%
FSI	1:0.83	1:1.67
Horizontal deviation	Nil	Nil
Floor deviation	Yes	Yes
Setback-Front	5'10"	4'0"
Setback-Rear	1'9"	1'0"
Setback-Rightside	8'0"	3'0"
Setback- Leftside	2'0"	--
Dwelling unit	G+1	G+4
Number of blocks	1	1
Unit deviation	Nil	Nil
Final Values		
Final Market Value (in Rs.)-Say	1,81,00,000/-	
Guideline Value (in Rs.)	12,97,075/-	
Forced Sale Value (in Rs.)-Say	1,62,90,000/-	90%
Insurable Value (inRs.)-Say	46,00,000/-	

DECLARATION:

I declare that

- I) I/ My Self has personally visited the property going to the site and inspected all items thoroughly.
- II) The statement off acts presented in this report are correct to the best of my knowledge.
- III) I do not have (if so for, specified in remarks of this report) interest in the subject property.
- IV) I have never been debarred or convicted by any court of law.
- V) The valuation report has been prepared for mortgage purpose.

Seal Signature of the Panel Valuer

Report Date: 21.11.2023


Er. K. JAYAKUMAR B.E., AMIE., FIV., C.Eng.,
Chartered Engineer & Registered Valuer
Registered Valuer for Income Tax & IBB
3/154, N.G.G.O. Colony, A. Sangampalayam,
Mahalingapuram (Po), POLLACHI - 642 002.
Cell : 82485 21943, 99655 54280

Longitudes: 77.00900

